

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 3 1963  
 6-3-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.Operator's full Name: Petroleum Inc.Complete Address: 352 N. Broadway, Wichita, KansasLease Name: Zrubelk Well No. # 1Location: Appro. SE SE SE Sec. 1 Twp. 30 Rge. 9 (E)(W) WCounty Kingman Total Depth 4284 Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Walker was instructed to plug the well as follows:

258' of 8 5/8" surface pipe, cement circulated with 225  
sacks. Fill hole with mud to 240', 1st cementing plug,  
1/4 sack hulls, cement with 20 sacks. Fill hole with mud  
to 40', 2nd cementing plug, 1/4 sack hulls, cement with  
10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent