

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 24 1964
 11-24-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Jack Sullivan of Sierra Petroleum Co. has this
 date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kans.

Lease Name: Griem Well No. # 1

Location: SW NW SW Sec. 1 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4250 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

238' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 235', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving