

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH


Locate well correctly on above  
Section Plat

Ford County Sec. 5 Twp. 25 Rge. 22 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE.  $\frac{1}{4}$ , SE.  $\frac{1}{4}$ , SW.  $\frac{1}{4}$   
Lease Owner Transwestern Oil Corporation  
Lease Name Hines Well No. I  
Office Address Box 108, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Rotary Dry Hole  
Date well completed 12/23/50 19  
Application for plugging filed 12/23/50 19  
Application for plugging approved 12/23/50 19  
Plugging commenced 12/23/50 19  
Plugging completed 12/23/50 19  
Reason for abandonment of well or producing formation Well was dry  
If a producing well is abandoned, date of last production X 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough  
Producing formation None Depth to top Bottom Total Depth of Well 4875 Feet  
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sands gravels shale and soil	Fresh water	0	200'	10 3/4"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was filled with rotary mud from total depth (4875) back to 247' where a wooden plug was set and 20 sacks cement was put in through the drill pipe. Hole was then filled with mud from top cement back to 30' where another wooden plug was set and 10 sacks cement was dumped on top plug which filled surface casing to top and overflowed into bottom cellar.

Surface casing was circulated with 200 sacks cement at time it was set

*Recd 12-30-54*

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Co.  
Address 1019 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
I, Roy Cook (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *Roy Cook*

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 1950

*Val Peterson*  
Notary Public.

My commission expires MAY 4, 1953



Faint, illegible text on the left side of the page, possibly bleed-through from the reverse side.

Faint, illegible text on the right side of the page, possibly bleed-through from the reverse side.



RECEIVED  
STATE CORPORATION COMMISSION  
JAN 4 1960  
CONSERVATION DIVISION  
Wichita, Kansas



HINES #1

SE $\frac{1}{4}$  SE $\frac{1}{4}$  SW $\frac{1}{4}$  Sec. 5-25S-22W, Ford County, Kansas

Rigging up Rotary Tools 11-25-50  
 Tearing down Rotary Tools 12-23-50

Run 8 Jts. 10 3/4" surface pipe. Set  
 at 247' and cemented with 200 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface clay and sand	0	100
Shale and shells	100	370
Shale and shells	370	550
Sand	550	670
Shale and shells	670	1475
Shale and red bed	1475	1515
Anhydrite	1515	1560
Shale and shells	1560	2070
Lime and shale	2070	2270
Broken lime and shale	2270	2390
Lime, shells and shale	2390	2475
Lime and shale	2475	2560
Broken Lime	2560	2605
Shale and lime	2605	2760
Broken lime	2760	2810
Lime and shale	2810	2920
Broken lime	2920	3000
Shale and lime	3000	4005
Lime	4005	4015
Lime and shale	4015	4110
Lime	4110	4490
Lime and shale	4490	4520
Lime	4520	4545
Lime and shale	4545	4775
Chat and lime	4775	4785
Lime	4785	4790
Lime and chat	4790	4800
Lime and shale	4800	4835
Lime	4835	4875

4875 Total Depth

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 Wichita, Kansas

JAN X 4 1951

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

*Don S. Packer*

Subscribed and sworn to before me this 3rd day of January, 1951.

*Notary Public*  
 Notary Public

My commission expires: March 22, 1952.

**PLUGGING**  
 FILE SEC 5 T 25 R 22W  
 BOOK PAGE 52 LINE 16