

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Ford County, Sec. 10 Twp. 25S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines SW/4  
Lease Owner Marden and Long  
Lease Name Hornung Well No. 1  
Office Address P. O. Box 1313, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 24 19 68  
Application for plugging filed May 24 19 68  
Application for plugging approved May 24 19 68  
Plugging commenced May 24 19 68  
Plugging completed May 24 19 68  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4950 Feet,  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	287.45'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged with mud from 4950' to 1130'; plugged at 1130' with 100 sacks of cement and mud to 290'. plugged at 290' with 30 sacks of cement and mud to 40'; plugged at 40' with 15 sacks of cement and hulls. Plug down at 10:30 P. M. May 24, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp, President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of May, 19 68

My commission expires December 31, 1969  
ELAINE H. TAYLOR  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS

Elaine H. Taylor  
Notary Public.

D R I L L E R S      L O G

#1 Hornung

CASING RECORD:  
287.45' of new 8-5/8"  
surface casing.

COMPANY: Marden and Long  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: SW/4  
Section 10-25S-22W  
Ford County, Kansas

TOTAL DEPTH:  
4950'

COMMENCED: May 8, 1968  
COMPLETED: May 24, 1968

ELEVATION: 2411' DF

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	100	Ran 287.45' of new 8-5/8" surface casing; set and cemented at 287.45' with 160 sacks of cement and 2% gel. Plug down at 4:00 A. M. May 10, 1968.
Clay & Blue Shale	100	315	
Red Bed & Blue Shale	315	565	
Red Bed, Shale & Shells	565	1345	
Shale	1345	1655	
Shale & Broken Lime	1655	2015	
Shale & Shells	2015	2430	
Lime & Shale	2430	2737	
Lime	2737	3127	
Lime & Shale	3127	3970	
Lime	3970	4500	
Lime & Chert	4500	4533	
Lime	4533	4769	
Lime & Chert	4769	4950	

Total Depth 4950'

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Ran electric log.

D. & A.

Plugged hole as follows: Plugged with mud from 4950' to 1130'; plugged at 1130' with 100 sacks of cement and mud to 290'; plugged at 290' with 30 sacks of cement and mud to 40'; plugged at 40' with 15 sacks of cement and hulls. Plug down at 10:30 P. M. May 24, 1968.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 27th day of May, 1968.

My Commission Expires:



*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public