


STATE OF KANSAS. STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 211 No. Broadway Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ford County, Sec. 10, Twp. 25, Rge. 22 (E) (WX) Location as "NE/CNW/SW" or footage from lines C NW SE Lease Owner Donald C. Slawson Lease Name Tasset "A" Well No. #1 Office Address 407 One Twenty Bldg. Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Date well completed 19 Application for plugging filed 2-6-65 19 Application for plugging approved 19 Plugging commenced 2-8-65 19 Plugging completed 2-15-65 19 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott Producing formation Depth to top Bottom Total Depth of Well 4932' Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. PULLED OUT contains 2744.57'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made plug back with sand to 4775', mixed and ran 5 sacks cement thru dump bailer. Mudded hole to 320', set 10' rock bridge, mixed and ran 35 sacks cement thru dump bailer. Mudded hole to 55' and set 10' rock bridge. Mixed and dumped 15 sacks cement to base of cellar.

RECEIVED STATE CORPORATION COMMISSION FEB 17 1965 CONSERVATION DIVISION Wichita, Kansas 2-17-65

(If additional description is necessary, use BACK of this sheet) Name of Plugging Contractor Southwest Casing Pulling Co., Inc. Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec. Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16 day of February, 19 65

My commission expires 24 October 1968 Sidney J. Miller Notary Public.

WELL LOG

Donald C. Slawson

10 25S 22W

COMPANY

Tassette "A" One

SEC.

NW, SE R.

LOG.

FARM

12 NO.

RIG. NO.

4932'

TOTAL DEPTH

116164 1/20/64

COMM.

Ho

SHOT OR TREATED

Murfin Drilling Company


CONTRACTOR

ISSUED

Ford

COUNTRY

KANSAS



ELEVATION

oil

PRODUCTION

CASING

20
15
12
13

10 5/8" 294' with 200 sacks
8
6
5 1/2" @4931' with 100 sacks

FIGURES INDICATE BOTTOM OF FORMATIONS

- 294' Surface hole
- 1020' Shale & sand
- 1130' Sand
- 1514' Sand, red bed
- 1520' Anhydrite
- 1720' Shale-sand
- 1980' Shale-shells
- 2570' Shale-shells
- 2710' Lime & shale
- 2815' Lime
- 3635' Lime-shale
- 3815' Lime
- 4161' Lime-shale
- 4844' Lime
- 4885' Chert-lime
- 4930' Lime "Miss."
- 4932' R. T. D.

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Kansas

State of

Sedgwick

County of

C. Robert Buford

ss:

Murfin Drilling

I, _____ of the _____ Tassette "A" #1 Company

upon oath state that the above and foregoing is a true and correct copy of the log of the _____ well.

5th

February

C. Robert Buford

Subscribed and sworn to before me this _____ day of _____ 19 _____

My Commission Expires:

ADELA MIZENER, Notary Public
My commission expires November 5, 1966

Adela Mizener
NOTARY PUBLIC