

10

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

7-13-64

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1964
CONSERVATION DIVISION
Wichita, Kansas
RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tomlinson-Kathol Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name Linscheid "A" Well No. 1

Location W/2 NW $\frac{1}{2}$ Sec. 19 Twp. 24 Rge. 7 (E) (W) X

County Reno Total Depth 3524'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour Noon Day 9 Month July Year 1964

The Above well was plugged as follows:

Hole filled with sand to 3500' and cemented with 4 sacks.

Hole filled with mud to 190'. Rock bridge set from 190' to 180' and

hole cemented with 20 sacks. Hole filled with mud to 40'. Rock bridge

set from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/13/64
INV. NO. 9464-W

Signed: [Signature]
Well Plugging Supervisor