

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION 21w-22w-SESEC. 26 TWP. 24 RGE. 12wDry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease L. JordanOperator W. L. Hartman Address Box #54 - Wichita - Kans.Field _____ County StaffordTotal Depth 4132 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 250 ft. Circulated with cement.
5 1/2" casing at 3743 ft. Plugged back from bottom
to 3100 ft with mud - Lane Wells Plug & cement.
Filled with chat from 3100 ft. to 3030 ft. with chat
Mixed 15 sacks of cement at 3030 ft. - Ripped off &
Pulled the 5 1/2" casing - Filled with mud to 250 ft
Set Rock Bridges & 15 sacks of cement at 250 ft - Mud to
30 ft - Plug & 10 sacks of cement at the surface -

RECEIVED
District Conservation Agent

Date 9-22-49 Conservation Div.

SEP 22 1949

STATE CORPORATION
COMMISSION
KANSAS

