

NO KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Gopher Oil & Gas Company

Complete Address: 5140 Valentine Road, Wichita, Kansas

Lease Name Reed Well No. # 1

Location C S/2 SE NW Sec. 26 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4117

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 11:45PM Day 30th Month June Year 1964

The Above well was plugged as follows:

202' of 8 5/8" surface pipe, cemented with 135 sacks. Fluid level was
up in the hole. 1st cementing plug and 1 sack hulls was pushed to 200',
and cemented with 25 sacks, through the drill pipe. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls,
and cemented with 10 sacks to base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/1/64

INV. NO. 9399-W

Signed: Archie Elving
Well Plugging Supervisor