

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1965
4-5-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Natural Gas & Oil Company

Complete Address: P. O. Box 1150, Great Bend, Kansas 67530

Lease Name McConnaughay Well No. # 4

Location SW NE SW Sec. 18 Twp. 24 Rge. 13 (E) (W)W

County Stafford Total Depth 4175'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 3rd Month April Year 1965

The Above well was plugged as follows:

239' of 8 5/8" surface pipe, cemented with 230 sacks. 4027' of 4 1/2" long
string, cemented with 150 sacks. Plug back to 3961'. Top perferation
3912'. Bottom of the hole was sanded to 3900', and cemented with 3 sacks.
3152' of 4 1/2" long string was recovered from the hole. Hole was flowing
with water and a squeeze job was necessary. Hole was full of heavy mud,
having been loaded through the anulus. 75 sacks of cement was pumped in
the surface pipe, through an 8 5/8" swage, to a pressure of 250 lbs.

This cementing was done by Knight Casing Pulling Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/5/65

INV. NO. 934-4