

15-185-19044-0000

Form CP-3  
Rev. 6-26-62

*llp*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 31 1965  
3-31-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Natural Gas & Oil Company

Complete Address: P. O. Box 1150, Great Bend, Kansas 67530

Lease Name McConnaughay Well No. # 2

Location NW NW SW Sec. 18 Twp. 24 Rge. 13 (E) (W)W

County Stafford Total Depth 3979'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 30th Month March Year 1965

The Above well was plugged as follows:

227' of 8 5/8" surface pipe, cemented with 150 sacks. 3969' of 2 1/2" long  
string, cemented with 125 sacks. Plug back to 3969'. Top perforation  
3908'. Bottom of hole was squeezed with 15 sacks of cement, plug and cem-  
ent pumped to 3832'. 3492' of 2 1/2" long string was recovered from the hole.  
Hole was flowing with water and a squeeze job was necessary. 10 sacks of  
Gel-Mud and 75 sacks of cement was pumped in surface pipe, through an 8 5/8"  
swage, to a pressure of 250 lbs. A wiping plug was run between the mud and  
the cement. This cementing was done by Knight Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/31/65

INV. NO. 910-W