

RP

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 25, 1967.

Operator's Full Name Great Bend Pipe & Supply Company, Inc.

Complete Address Drawer "B", Great Bend, Kansas 67530

Lease Name McConnaughay Well No. # 3

Location NE NE SW Sec. 18 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4159'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:30 A.M. Day 23rd Month August Year 1967

The above well was plugged as follows:

220' of 8 5/8" surface pipe, cement circulated. 4156' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 4100', and cemented with 5 sacks, through the dump bailer, with cement
from 4100' to 4060'. 3250' of 5 1/2" long string was recovered from the hole.
Hole was making water and was squeezed. 10 sacks of Gel-Mud and 80 sacks
of cement was pumped into the surface pipe, through an 8 5/8" swage, to
a pressure of 300 lbs., with cement from 240' to the base of the cellar.

A wiping plug was run between the Mud and the cement. This cementing was
done by Knight Casing Pulling Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 8-24-67
AV. NO. 6200-W