


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ford County, Sec. 11 Twp. 25S Rge. (E)-22-(W)
Location as "NE/CNW/SW" or footage from lines. C NW SW
Lease Owner Okmar Oil Company
Lease Name Imel Well No. 2
Office Address 1130 Vickers Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-11 19 73
Application for plugging filed 8-11 19 73
Application for plugging approved 8-11 19 73
Plugging commenced 8-11 19 73
Plugging completed 8-11 19 73
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	280	8-5/8"	273'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 660', plug, 70 sx cement;
Fluid to 240', plug, 20 sx cement;
Fluid to 40', plug, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
Address 701 First Nat'l Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 73

My commission expires August 25, 1976

Ella Priess
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Com. Expires Aug. 25, 1976

Ella Priess
Notary Public.

DRILLERS' LOG

OKMAR OIL COMPANY
 No. 2 Imel
 C. NW SW, Sec. 11-25S-22W
 Ford County, Kansas

Elevation: 2403 K.B.

Commenced: 8-4-73
 Completed: 8-11-73

Surface Casing: 273' of 8-5/8"
 cemented w/175 sx 60-40 Posmix,
 38 cc. 8-4-73

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 280
Shale	280 - 290
Shale & Sand	290 - 1480
Shale	1480 - 1515
Anhydrite	1515 - 1540
Shale	1540 - 1875
Shale & Salt	1875 - 2300
Shale & Lime	2300 - 2570
Lime & Shale	2570 - 3940
Sand & Shale	3940 - 4170
Lime	4170 - 4830 T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 16 1973
 CONSERVATION DIVISION
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 15th day of August 1973.

My Commission Expires:
 August 25, 1976

Ella Priess
 Ella Priess, Notary Public

Ella Priess
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Com. Expires Aug. 25, 1976