


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ford County, Sec. 11 Twp. 25 Rge. 22 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C of SE NW
Lease Owner Okmar Oil Company
Lease Name W Imel #1 Well No.
Office Address Hays, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/19/77 19
Plugging completed 5/31/77 19
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Thomas
Producing formation Depth to top Bottom Total Depth of Well 4789
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	275	none
				5 1/2"	4780	2850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Squeezed bottom hole with 35 sacks common cement. Pumped plug to 4500', shot pipe
at 3940', 3805', spotted 80 barrels oil and pumped plug to 3705'. Shot pipe at
3525', 3330', 3100', 3010', 2910', 2810', pulled 89 joints. Squeezed hole with
3 sacks hulls, 10 sacks gel and 50 sacks common 4% gel, 10 sacks gel. Released
plug, 35 sacks common 4% and 5 sacks gel, displaced with 15 sacks common 4% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 77

My commission expires



Margaret Melcher
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUN 06 1977

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' LOG

OKMAR OIL COMPANY
 Imel No. 1
 C SE NW, Sec. 11-25S-22W
 Ford County, Kansas

Elev: 2401 G.L.

Commenced: 4-4-72
 Completed: 4-13-72

Surface Casing: 281' of
 8-5/8" cemented w/175 sacks
 cement, 38 cc. 4-4-72

FORMATIONDEPTH

Surface Hole	0 - 289
Shale	289 - 590
Sand	590 - 780
Shale & Shells	780 - 850
Red Bed, Sand & Shale	850 - 1498
Anhydrite	1498 - 1523
Shale & Shells	1523 - 1665
Shale	1665 - 1990
Salt & Shale	1990 - 2325
Lime & Shale	2325 - 2580
Lime	2580 - 2810
Lime & Shale	2810 - 3020
Lime	3020 - 3270
Lime & Shale	3270 - 3680
Lime	3680 - 4795 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 19th day of April, 1972.

My Commission Expires:
 August 25, 1972

Ella Priess

Ella Priess, Notary Public

