

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Stafford County, Sec. 13 Twp. 24 Rgd. 1 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NE
Lease Owner Knight Casing Pulling Co., Inc.
Lease Name Johnson #3 Well No.
Office Address Chase, Kansas 67524
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/29/72 19
Plugging completed 5/4/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3793' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	249	none
				7"	3786'	1226'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, pushed plug to 3700' and dumped 6 sacks of cement.
Shot pipe at 1480', 1388', 1259', pulled pipe. Set 10' rock bridge
at 200' and dumped 4 yards ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.

Name of Plugging Contractor CHASE, KANSAS
Address

STATE OF KANSAS, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of May, 1972

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975


Notary Public.

E. H. MOORE, INC.
Ira C. Johnson No. 3.

SEC. 13 T. 24 R. 11W
NW SE SW

Total Depth. 3808'
Comm. 8-8-38 Comp. 8-26-38
Shot or Treated.
Contractor. Zephyr Drlg. Co.
Issued. 12-17-38

County. Stafford



CASING:
10 3/4" 266'10"
7" 3786'3"

Elevation.

Production. Pot. 3126 B.

Figures Indicate Bottom of Formations.

sand	74
sand & red bed	205
sand rock	230
shale & shells	240
shale & red rock	272
sand & shells	304
red rock & shale	824
shale & shells	1200
salt	1425
salt & shale	1605
shale & lime	1662
lime	1849
shale & lime	1964
lime	2020
shale & lime	2633
lime	2663
shale & lime	2684
lime	2751
shale & shells	2807
shale & lime	2890
lime Topeka	2985
shale	3000
lime	3055
shale & lime	3111
shale	3155
lime	3262
shale & shells	3290
shale & lime	3384
shale	3397
lime	3500
choert	3518
lime	3568
shale & lime	3790
sand	3808
Total Depth.	

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1972

CONSERVATION DIVISION
Wichita, Kansas

Top Lansing 3385
Top Misener 3789