

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUG
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION
CONSERVATION DIVISION. - PLUGGING SECTION
200 COLORADO DERBY BUILDING. 15.185-22
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,258-40001

NE SE SE, SEC. 30, T 24 S, R 13 W

15.185-22258-0001

990 _____ feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name McCandless Well # 1

Operator: Woodman-Iannitti Oil Company

County Stafford

Name & Address P.O. Box 308

Well Total Depth 4010 130.32 feet

Great Bend, KS 67530-0308

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated.

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 24 Month: 3 Year: 1994

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

vars: 5½" at 4008' w/100 sx cement, PBTD 3989', Perfs at 3960-67, 3946-53'

1st plug sand back to 3900' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 24 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5½" casing back to 3900' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3019' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

1. ~~State~~ ~~XXXXXXXXXX~~ observe this plugging.

DATE 4-4-77

INV. NO. 40851

Signed Dean Kank CONSERVATION DIVISION
(TECHNICIAN) Topeka, Kansas

FORM CP-
Rev. 01.