

4-041942

10-22

E-23,813-0005

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-20,492-0001

NE SE NW _____ / 4 SEC. 28, 11 S, 22 W
3630 _____ feet from S section line
2970 _____ feet from E section line

Operator license# 5030

Lease: Beren Ries Well # 1

Operator: Vess Oil Corporation

County: Trego 130.81

Address: 8100 E. 22nd Street
N. Building #300
Wichita, Kansas 67226

Well total depth 4025 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 270 Feet
W/140 sxs cmt.

Aband. oil well _____, Gas well _____, Input well X, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 20 Month: October Year: 1997

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 316-682-1537

Were: 4 1/2" casing set at 3990' w/200 sxs cement. Perfs at 3575' - 3950'.
Ordered 100 sxs 60/40 pozmix.
Squeezed 4 1/2" casing at 1184' - 1643' with 550 sxs. Tubing and packer at 3499' cemented
to surface with 250 sxs. Rods stuck in hole with top at 1775'.

Plugging Proposal Received by: Dennis Hamel 11-25-97
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00 P.M. Day: 22 Month: October Year: 1997

Actual plugging report: Rigged-up perforators to perf tubing and casing at 1675' (anhy).
Pressured-up tubing to 2000# P.S.I. Cement from squeeze apparently behind pipe. Pulled up
and shot casing at 1200'. Pressured-up to 2000# P.S.I. Pulled-up and shot casing at 975' -
pumped in 30 sxs cement to squeeze base of Dakota to 900#. Rigged-up cemmeters to 8 5/8"
S.P. Pumped 35 sxs cement.

Remarks: _____
Condition of casing(in hole): GOOD _ BAD X Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING X Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DEC 10 1997

DATE _____
INV. NO. 49631

Handwritten initials