

8-28

4-041926

E-23,813-0001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-20,731-0001

SW SE NE /4 SEC. 28, 11 S, 22 W
2970 feet from S section line
990 feet from E section line

Operator license# 5030

Lease: Honas A Well # 3

Operator: Vess Oil Corporation

County: Trego 130.81

Address: 8100 E. 22nd Street
N. Building #300
Wichita, Kansas 67226

Well total depth 4025 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 249 Feet
W/175 sxs cmt.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 28 Month: August Year 1997

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 316-682-1537

Were: 4 1/2" casing set at 4003' w/1000 sxs cement - circulate at surface.
Perfs at 3622' - 3625'. W.L.M. at 3623' - T.O.F. at 2500'.
Ordered 200 sxs 60/40 pozmix - 10% gel - 1/4# F.C. plus 400# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 1997

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 12:30 P.M., Day: 28, Month: August, Year: 1997

Actual plugging report: 8 5/8" S.P. R.U. Cementers. Squeezed casing to 600# with 10 sxs cement. S.I.P. 500#.
R.U. Cementers to 4 1/2" casing. Squeezed 185 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
SEP 25 1997

DATE

49109