

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20794-00-00
Spot: CN2SWSE Sec/Twnshp/Rge: 25-24S-14W
990 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: MEYER Well Number: 1
County: STAFFORD Total Vertical Depth: 4192 feet

Operator License No.: 3910
Op Name: HALE, L.D.
Address: 15000 TIMBER LAKE RD.
WICHITA, KS 67230

Production Casing Size: 5.5 feet: 4189 WITH 450 SX CMT
Surface Casing Size: 8.625 feet: 468 WITH 325 SX CMT

\$136.24

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2003 3:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 2050' & 5 SX CMT. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/28/2003 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 2350'. PERFS AT 2122-2127'. SANDED BACK TO 2050' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
APR 14 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID & CEMENT. RECOVERED 1810' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 4-15-03

INV. NO. 2003061414

FORM 2/03