

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20732-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 25-24S-14W  
413 feet from S Section Line, 3151 feet from E Section Line  
Lease/Unit Name: KOELSCH Well Number: A-2  
County: STAFFORD Total Vertical Depth: 2199 feet

Operator License No.: 3493  
Op Name: FISHER, REGINALD D.  
Address: 110 N. EXCHANGE  
ST. JOHN, KS 67576

Conductor Pipe: Size feet: 71.47  
Surface Casing: Size 8.625 feet: 287 WITH 250 SX CMT  
Production: Size 4.5 feet: 2198 WITH 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/06/2002 12:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 1875' & 4 SX CMT. 1ST PLUG AT 850' WITH 50 SX CMT. 2ND PLUG AT 325' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/06/2002 2:00 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 2170'. PERFS AT 1931-35'. SAND BACK TO 1700' WITH 4 SX CMT WITH BAILER. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 850'. 2ND PLUG SPOT 50 SX CMT AT 315'. 3RD PLUG SPOT 10 SX CMT AT 0-40'. GOOD CIRCULATION THROUGHOUT JOB.

RECEIVED  
SEP 13 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1410" OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

SEP 09 2002

VOICE MAIL  
DATE 9-17-02

NO. 2003060510