

To: 1 051759
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-9

API NUMBER 15- 057-20,521-0000
C NW NE, SEC. 13, T 25 S, R 22 W/E
660 feet from NX section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Co. Inc.
Name & Address: 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Aistrup Farm Well # 1 "C"
County Ford
Well Total Depth 4875 158.44 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____
Plugging Contractor Pickrell Drilling Co. Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 9 Month: 12 Year: 19 93
Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Co. Inc. (phone) 316-262-8427

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1503-1522'
1st plug at 1520' with 50 sx cement, 2nd plug at 680' with 60 sx cement,
3rd plug at 330' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 3:30 a.m. Day: 9 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement,
2nd plug at 680' with 60 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

12-14-93

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1993

INVOICED
DATE 12-15-93
INV. NO. 39541

Signed Richard Lacey (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 11-17-93

State of Kansas 15-057-20,521-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SEAT Yes X No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 - 22 - 93
month day year

Sec NW NE Sec 13 Twp 25 S. Rg 22 East X West

OPERATOR: License # 5123
Name: Pickrell Drilling Co. Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Don Beauchamp
Phone: 316-262-8427

660 feet from North line of Section
1980 feet from East line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 5123/
Name: Pickrell Drilling Co. Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ford
Lease Name: Aistrup Farm Well #: #1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
X. Oil ... Enh Rec ... Infield X. Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal X Wildcat ... Cable,
... Seismic: ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 2388' feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 145'
Depth to bottom of usable water: 250' 650' ✓
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: (300') 200'
Length of Conductor pipe required: None
Projected Total Depth: 4900'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond X ... other

If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:

DWR Permit #:
Will Core Be Taken? ... yes X no
If yes, proposed zone:

Exp. 5/12/94

AFFIDAVIT 200' Alt. II Reg

RECEIVED

KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Doyle F.
SPUD DATE 11-29-93 INIT. CA
LENGTH SURFACE PLANNED 290
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 3/4" @ 221' CONDUCTOR
ANHYDRITE T-1503 B-1522 ELEVATION
TD 4875 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1520 Ft. W/ 50 SX
1/2 Base Anyh. @ 680 Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 330 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN R.L. DATE
TYPE OF CEMENT 60/40 per 6 bags 1/4 Flostal
STARTING TIME 2:00 (PM) DATE 12-9-93
COMPLETION TIME 3:30 (PM) DATE 12-9-93
CEMENT COMPANY A Red

RECEIVED
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas