

To: 1080034  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

15-075-00131-0000  
API NUMBER 15- Drill completion date 11/24/61

App. C SW SEC. 30, T 22 S, R 40 W/E

1250 feet from S section line

4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4680

Lease Name HCU Well # 3020

Operator: American Exploration Company

County Hamilton 85.31

Name: 1331 Lamar, Ste. 900

Well Total Depth 2625 feet

Address Houston, TX 77010-3088

Conductor Pipe: Size          feet

Surface Casing: Size 8 5/8 feet 133

Abandoned Oil Well          Gas Well X Input Well          SWD Well          O&A         

Other well as hereinafter indicated         

Plugging Contractor J.W. Gibson License Number 5866

Address P.O. Box 1383, Guymon, OK 73942

Company to plug at: Hour: 10:30 a.m. Day: 9 Month: 4 Year: 19 96

Plugging proposal received from Tom Patton

(company name) J.W. Gibson (phone) 405-338-0664

Work: 4 1/2" at 2620' w/700 sx cement, circulated 160 sx to pit, PBTD 2615', Perfs at 2602-12'

1st plug set CIBP at 2550' with 2 sx cement on top,

2nd plug perforate at 1150' and pump 100 sx cement,

3rd plug at 650', circulate to surface with cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part          None         

Operations Completed: Hour: 2 p.m. Day: 9 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2540' with 2 sx cement on top,

2nd plug ran tubing to 1250', loaded hole with mud, and pumped 91 sx Class C cement-

circulated to surface. RECEIVED

3rd plug pulled tubing and topped off 4 1/2" casing with 10 sx cement KANSAS CORPORATION COMMISSION

APR 17 1996

4-17-96

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Used Class C cement by Gibson. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE APR 18 1996

Signed Kevin P. Smith  
(TECHNICIAN)

INV. NO. 45334