

To: R 1020811
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-21 API NUMBER 15-093-21,356-0000
N/2 N/2 SW SEC. 5, T 22 S, R 38 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Operator: Amoco Production Company
Name & Address P.O. Box 800, Room 925
Denver, CO 80201

2310 feet from S section line

3455 feet from E section line

Lease Name Martin Well # 1-5

County Kearny 112.28

Well Total Depth 3455 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 2326

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Liberal, KS

Company to plug at: Hour: 2 p.m. Day: 21 Month: 10 Year: 19 94

Plugging proposal received from Spanky

(company name) Halliburton (phone) 800-853-3555

Work: 5 1/2" at 3455' w/445 sx cement, PBD 3454', Perfs at 2694'-3290' (10 sets)

1st plug pump 2 sx hulls and 164 sx cement and wiper plug to 750', pressure up,

2nd plug perforate 5 1/2" casing at 700', circulate cement to surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 21 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 164 sx cement and wiper plug to

750', pressured up,

2nd plug perforated 5 1/2" casing at 700', pumped 132 sx cement circulated to surface.

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1994

Remarks: Used 65/35 Class C cement w/6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form)
CONSERVATION DIVISION
WICHITA, KANSAS

I (do not) ~~XXXXXX~~ observe this plugging.

INVOICED

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 10-21-94

INV. NO. 41552