

10-31

To: 1 090024
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13- 057-20,453-0000
SE SE NW, SEC. 11, T 25 S, R 22 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6016
Operator: Condor Energy, Inc.
Name & Address: P.O. Box 108
Great Bend, KS 67530

Lease Name Imel Well # A-2
County Ford
Well Total Depth 4895 159.08 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 31 Month: 10 Year: 19 90

Plugging proposal received from Bill Fulls
(company name) Kelso Casing Pulling, Inc. (phone) 316-792-1751

were: 5 1/2" at 4894', Perfs at 4787-89, 4792-95'
1st plug sand back to 4735' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 20 sx gel at 1600', 3rd plug pump 50 sx cement at 1540',
4th plug pump 50 sx cement at 760', 5th plug pump 120 sx cement at 470',
6th plug pump 50 sx cement down backside.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 31 Month: 10 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4735' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 7 sx gel at 1600', good circulation,
3rd plug pulled to 1540' and pumped 50 sx cement,
4th plug pulled to 760' and pumped 50 sx cement,
5th plug pulled to 470' and pumped 120 sx cement, 6th plug pulled to 150' and pumped 20
sx cement, 7th plug circulated 15 sx cement on top.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-9-90
INV. NO. 29922

observe this plugging.
NOV 5 1990 Signed [Signature] (TECHNICIAN)
11-5-90