

1 030947

5-23-88

API NUMBER 15- 057-20,444-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION W/2 E/2 NW, SEC. 11, T 25 S, R 22 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9421  
Operator: Boger Brothers Drilling Inc.  
Name & Address: P.O. Box 723  
Great Bend, KS 67530

Lease Name Imel "A" Well # 1  
County Ford 158.75  
Well Total Depth 4885 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling Inc. License Number 9421  
Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 23 Month: 5 Year: 19 88

Plugging proposal received from Dale Smith

(company name) Boger Brothers Drilling Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2383' GL  
Anhydrite 1502-1530'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 850' with 80 sx cement,  
3rd plug at 450' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 a.m. Day: 23 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,  
2nd plug at 850' with 80 sx cement,  
3rd plug at 450' with 40 sx cement,  
4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5-24-88  
MAY 24 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

Signed Steve H... (TECHNICIAN)

DATE 5-25-88  
INV. NO. 20869

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... January 20, 1988

API Number 15-057-20,444-0000

OPERATOR: License # 9421
Name Boger Brothers Drilling Inc.
Address P. O. Box 723
City/State/Zip Great Bend, KS 67530
Contact Person Dale Smith
Phone 316-792-8151

W/2 E/2 NW Sec. 11 Twp. 25 S, Rg. 22 XX West
3960 Ft. from South Line of Section
3630 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9421
Name Boger Brothers Drilling Inc.
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 990' feet
County Ford
Lease Name Inel. "A" Well # 1
Ground surface elevation 2400 Est. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 150
Depth to bottom of usable water 400
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 420
Conductor pipe required None
Projected Total Depth 4800 feet
Formation Mississippian

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 1-15-88 Signature of Operator or Agent [Signature] Title Geologist

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 420 feet per Alt.
This Authorization Expires 7-19-88 Approved By [Signature] 1-19-88

EFFECTIVE DATE: 1-24-87
Made in 5-11-88 set 420' of 8 5/8
W/2 E/2 NW Sec. 11 Twp. 25 S, Rg. 22 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Plug length (ft.). Includes entries for 1st through 5th plugs and a Rathole.

Vertical list of well parameters:
PUSHER Dale Smith
TD 4885 FORMATION
SURFACE PIPE 8 5/8 @ 442
ANHYDRITE 1502 ELEVATION 23236
STARTING TIME & DATE 9:44
COMPLETION TIME & DATE 11:20 5-23
Base only
1st PLUG @ 1530 FT. W/ 50 SX
2nd PLUG @ 850 FT. W/ 80 SX
3rd PLUG @ 450 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Hall
TECHNICIAN 60/40 w/ 6 7/8 gel

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1988
CONSERVATION DIVISION
Wichita, Kansas