

State of Kansas



15. 167. 00675. 00. 00

FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 8 1953

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. P. E. Plouffe of Blackstone Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Don McKellar guarantees payment of the plugging fee.

Operator's full Name: Don McKellar Oil Explorations

Complete Address: Box 173, Salina, Kansas

Lease Name: Mollhagen Well No. # 1

Location: NE NE SW  
G/EL NE SE Sec. 2 Twp. 15 Rge. 11 (E) (W)

County Russell Total Depth 3250 Oil Well

Gas Well    Input Well    SWD Well    D & A X    Lost Hole   

Mr. P. E. Plouffe was instructed to plug the well as follows:

8 5/8" 325' Cwc.

Filled hole with heavy mud to 300'; set solid plug;

displaced 25 sx cement thru drill pipe. Mud to 40'; 1/2

sx hulls; plug; displaced 10 sx cement, cementing to base

of cellar.

Very truly yours,

*John T. ...*  
 Conservation Division Agent