



15.167.30/35.00.00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Louis M. Mai of Louis M. Mai has this date requested permission to plug the following described well:

Mr. Louis M. Mai guarantees payment of the plugging fee.

Operator's full Name: Louis M. Mai

Complete Address: P. O. Box 33, Russell, Kansas 67665

Lease Name: Anna Bond Well No. # 9

Location: NW NW NE Sec. 22 Twp. 14 Rge. 13 (E)(W) W

County: Russell Total Depth 3236 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Don Wolfe was instructed to plug the well as follows:

8 5/8" csg. 482' Cwc. Perf. 2282'

Sanded hole back to 2250' & dumped 4 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud, released plug, & displaced

100 sax cement with Allied Cementing Company's pump truck, cementing

from 350' to base of cellar.

Very truly yours,

Don Wolfe  
Conservation Division Agent