

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1965

CONFIDENTIAL

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Warren Davis of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Hellar Drilling Company, Inc.

Complete Address: 1014 Union Center, Wichita, Kansas

Lease Name: Doran Well No. # 1

Location: SE SW SW Sec. 2 Twp. 24 Rge. 15 (E) (W) W

County Stafford Total Depth 4110' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

246' of 8 5/8" surface pipe, cement circulated with 245 sacks.

Fill hole with drilling mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent