

State of Kansas



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 12 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Mr Sterling Glaves of E.H. Adair Oil Company has this
 date requested permission to plug the following described well:

Mr. Glaves guarantees payment of the plugging fee.

Operator's full Name: E.H. Adair Oil Company

Complete Address: 1005 E. 2nd, Wichita, Kansas.

Lease Name: Chavez Well No. 2

Location: C. SE. SE Sec. 26 Twp. 24 Rge. 1 (E)(W)


County Harvey Total Depth Oil Well

Gas Well Input Well SWD Well D & A x Lost Hole

Mr. Glaves was instructed to plug the well as follows:

Fill hole w/ 36 vis mud from T.D. 2724' back to 240' set a bridge and
run 20 sax cement. Fill hole w/ 36 vis mud from 170' back to 35' set
a bridge and run 8 sax cement. Fill rat hole w/ mud and 2 sax cement.

Very truly yours,


 Conservation Division Agent