

15.167.00642.00.00

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) -
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1964
5-18-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. F. R. Hoyt of Shields Oil Producers, Inc. has this date requested permission to plug the following described well:

Mr. Robert J. Shields guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas

Lease Name: Hilgenberg Well No. # 1

Location: SE NE SE Sec. 18 Twp. 15 Rge. 12 (E) (W) W

County Russell Total Depth 3315 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

8 5/8" 284' Cwc.

Sanded hole back to 3300' & dumped 4 sax cement with
dump bailer. Pulled pipe. Bailed hole dry to 280'; set
rock bridge & displaced 30 sax cement. Mud to 40'; set
rock bridge & displaced 10 sax cement, cementing to base
of cellar.

Very truly yours,
Dow Truman