



GR

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. James B. Develin guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 240 Sutton Place, Wichita, Kansas

Lease Name: Kaufman Well No. # 1

Location: SW NE <sup>SE</sup> SW Sec. 14 Twp. 15 Rge. 12 (E)(W) W

County: Russell Total Depth 3275 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Claude Norwood was instructed to plug the well as follows:

8 5/8" 251' Cwc.

Circulated hole with heavy mud to 480', set plug. & displaced 40 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru

drill pipe. Mud to 40'. 1/2 sax hulls. plug. & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to

base of cellar.

Very truly yours,

Don L. Linn  
Conservation Division Agent