



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E.H. Adair Oil Company

Complete Address: 1005 E. 2nd, Wichita, Kansas.

Lease Name Chavez Well No. 1

Location C SE SE Sec. 26 Twp. 24 Rge. 1 (E) (W)

County Harvey Total Depth 3724'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Company Tools

Address: Same License No. Rotary

Operation Completed: Hour 2;PM Day 8 Month 12 Year 63

The Above well was plugged as follows:

Filled hole w/ 36 vis mud from T.D. 3724' back to 240' set a halco plug 1/2 sak hulls
and ran 20 sax cement from 230' back to 170'. Filled hole w/ 36 vis mud from 170' back
to 35' set a halco plug 1/4 sak hulls and ran 8 sax cement from 25' back to zero 3'
below ground level. Filled ratthole w/ mud and 2 sax cement 3' below ground level.
8.5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging/Supervisor

DATE 12-12-63
INV. NO. 87 25-E