

15.167.00066.00.00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-29

LOCATION SE-SE-NW

SEC. 2 TWP. 15 RGE. 14W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 3 Lease Michel

Operator Alky Oil Co Address 611 Kennedy Bldg Tulsa Okla.

Field _____ County Russell

Total Depth 2400 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address 2905 16th St. Great Bend Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" @ 706' C.W.C. Oil string was
5 1/2" set 2299 w/75 st Cemu. L.W.P. 2284' Top Perf.
2269'. Filled back with sand to 2250' and
dumped 5 st of Cemu. With dump bails. Shot
off and pulled 5 1/2" casing. Filled hole with
mud to 270' set rock bridge, mixed and run
20 st of Cemu. mud to 35' set rock bridge and
10 st of mixed Cemu. to base of collar.

12-24-53

Warren H. Warner
District Conservation Agent

Date 12-22-53

PLUGGING
FILE SEC. 2 T. 15 R. 14W
BOOK PAGE 148 LINE 29