


STATE OF KANSAS
STATE CORPORATION COMMISSION

15.167.00675.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Russell County, Sec. 2 Twp. 15S Rge. 11 XXX (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Don McKellar Oil Explorations
Lease Name Mollhagen Well No. 1
Office Address Box # 173, Salina, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed November 4, 1963
Application for plugging filed November 1963
Application for plugging approved 19
Plugging commenced November 4, 1963
Plugging completed November 4, 1963
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Shale		0	155			
Shale		155	325	8 5/8	325	Noen

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Built bridge at 300 ft. with wood and rock and half sack of hulls. Poured 25 sacks cement through drill pipe to 300 ft. Filled with mud to 40 ft. of top. Built top plug with wood, hulls and 10 sacks cement. Hole plugging completed at 5:00 P.M., Nov. 4, 1963.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas

STATE OF Kansas COUNTY OF Saline, ss.
Don McKellar (Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Don McKellar*
Box # 173, Salina, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13th day of November, 1963

My commission expires Sept 27, 1967 *Julia M. Lynch* Notary Public.

13. 167. 00675. 00. 00

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DON MC KELLAR OIL EXPLORATION
Farm- Mollhagen No. 1

SEC. 2 T. 15 R. 11W
NE NE SW

Total Depth. 3250'
Comm. 10-28-63 Comp. 11-4-63
Shot or Treated.
Contractor. Blackstone Drig.
Issued. 2-1-64

County Russell
KANSAS



Elevation. 1700' KB

Production. DRY

8 5/8" 325' cem w/ 135 ax

Figures Indicate Bottom of Formations.

clay & shale	155
shale	325
shale & shells	1345
shale & lime	1580
lime & shale	2150
shale & sand	2225
lime	2280
lime & shale	2565
lime	2790
lime & shale	2865
lime	3225
Conglomerate	3226
Arbuckle	3250
Total Depth	

TOPS: SMP	
Foraker	1933
Indian Cave	2078
Tarkio Sand	2155
Tarkio Lime	2224
Howard	2437
Topeka	2475
Hessner	2765
Toronto	2785
Douglas	2797
Brown Lime	2862
Lansing Kansas City	2874
Base Kansas City	3143
Marmaton Lime	3147
Pennsylvanian Conglomerate	3198
Simpson	3208
Arbuckle	3227

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1964

CONSERVATION DIVISION
Wichita, Kansas