

MAR 11 1999

WICHITA, KS 3-11-99

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Meyer

WELL NUMBER 1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

LEASE OPERATOR Dunne Equities Operating, Inc.

SEC. 2 TWP. 24 RGE. 15 (E) or (W)

ADDRESS 8100 E. 22nd St. North #1100 Wichita, KS 67226-2311

COUNTY Stafford

PHONE# (316) 684-6508 OPERATORS LICENSE NO. 32166

Date Well Completed _____

Character of Well _____

Plugging Commenced 2-23-99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-25-99

The plugging proposal was approved on 2-22-99 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 7/8	297	
				4 1/2	4178	2053

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
Mixed 2 SX hulls & 20 SX cmt. from 4067 to 3867. Recovered 2053.
Pulled 4 1/2 to 910. Mixed 50 SX plug from 910 to 760. Pulled to 330. Mixed
50 SX plug from 330 to 180. Pulled 4 1/2. Tagged plug @ 209. Mixed 10 SX plug from
40 to 0. Cut off & capped 8 7/8 3 ft. below ground level.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dunne Equities Operating Inc

STATE OF Kansas COUNTY OF Adair, ss.

Monna M. Armistead (Employee of Operator) or (Operator)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
 statements, and matters herein contained and the log of the above-described well as filed i
 the same are true and correct, so help me God.

(Signature) Monna M. Armistead

(Address) 8100 E 22nd St. #1100 67226-2311

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1999

Alexis R Wood
 Notary Public

My Commission Expires:

