

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford

County. Sec. 2 Twp. 24 Rge. (E) 15 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE SE

Lease Owner Westgate-Greenland Oil Company, et al

Lease Name Munz Well No. 1

Office Address 1009 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed July 3, 1952 19

Application for plugging filed July 3, 1952 (orally) 19

Application for plugging approved July 3, 1952 19


Plugging commenced July 4, 1952 19

Plugging completed July 4, 1952 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	200	10 3/4"	200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4155 to 195 feet  
Bridged solid with rock at 195 feet and ran 25 sacks cement  
Filled hole with heavy mud from 145 feet to 35 feet  
Set plug and ran 10 sacks cement to cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 9 1952 7-9-52  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Jackson Drilling Corporation  
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler  
1009 Central Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of July 19 52  
Esther Russell  
Notary Public.

My commission expires May 25, 1953 23-8390-s 6-51-20M

PLUGGING  
FILE SEC 2T 29R 152  
BOOK PAGE 28 LINE 23

## DRILLERS LOG

COMPANY: Westgate-Gremland Oil Company  
 CONTRACTOR: Jackson Drilling Corporation  
 WELL: Munz #1  
 LOCATION: SE SE SE Section 2-24S-15W  
 Stafford County, Kansas  
 COMMENCED: June 18, 1952  
 COMPLETED: July 3, 1952  
 ELEVATION: 2005 DF.

0	to	40	Sand- clay
40	to	100	Sand and shale
100	to	200	Shale and shells
200	to	300	Shale
300	to	425	Red bed and shale
425	to	475	Sand
475	to	913	Red bed- shale
913	to	940	Anhydrite
940	to	1770	Shale and shells
1770	to	1930	Lime and shale
1930	to	2185	Lime
2185	to	3150	Lime and shale
3150	to	3520	Lime
3520	to	3524	H. shale
3524	to	3650	Lime and shale
3650	to	3915	Lime
3915	to	3961	Lime and shale
3961	to	4020	Conglomerate
4020	to	4066	Chert and lime
4066	to	4083	Chert
4083	to	4095	Simpson shale
4095	to	4115	Shale-sand
4115	to	4155	Arbuckle lime

Set 200 feet of 10 3/4" 32# surface pipe. Cemented with 225 sacks cement and 3 sacks calcium chloride.

Drill Stem Test: 4114-23, open 1 hour, recovered 1150' sulphur water, BHP 1260# FG 510#.

TOPS: Anhydrite	913	Lansing	3657
Heebner	3513	Viola	4015
Toronto	3536	Simpson	4060
Brown Lime	3649	Arbuckle	4113

Schlumberger run.

DRY, PLUGGED AND ABANDONED

## C E R T I F I C A T E

I, Don Allen, do hereby certify that the above and foregoing is a true and correct copy of log of the Munz #1, SE SE SE Section 2-24S-15W, Stafford County, Kansas, as reflected by files of the Westgate-Gremland Oil Company.

RECEIVED  
 CORPORATION COMMISSION

*Don Allen*  
 Don Allen

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 7th day of July, 1952.

PLUGGING  
 FILE SEC-2 T 24 S 15 W  
 BOOK PAGE 28 LINE 23  
 My commission expires May 25, 1953.

*Esther Russell*  
 Notary Public