

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Stafford County, Sec. 32 Twp. 24 Rge. 13 (E) W (W)
Location as "NE/CNW/SE" or footage from lines SW NE SE
Lease Owner R.W. Shields
Lease Name Glasscock #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-19-58 19
Plugging completed 9-30-58 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4236 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	none
				5-1/2"	4233'	2037'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4235' and found it open.
Filled w/sand to 4220' and dumped 5 sacks of cement. Pulled 15 jts 5 1/2" casing and circulated with mud from pit. Pulled rest of pipe, cleared hole and tried to bail hole of mud, could not. Set a rock bridge at 240' and dumped 8 sacks of cement with dump bailer. Bailed hole to top of cement bridge and ran 12 more sacks of cement. Mudded the hole to 35', set a rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of October, 19 58

9-27-62

Thomas V. Boyer

Notary Public.

My commission expires _____

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 32 T 23 R 13 W
BOOK PAGE 130 LINE 26

WELL LOG

No. 1 Glasscock

Chief Drilling Co. - Sunray - Shields
 Box 97
 Great Bend, Kansas

Elevation: 1940° DF
 1938° GL
 1943° KB

No. 1 Glasscock ²⁴
 SW NE SE, Section 32-23-13W
 Stafford County, Kansas

Commenced: 7-15-58
 Completed: 7-26-58


Contractor: Chief Drilling Co., Inc.
 Rotary: 0-4236'

Casing Record: Set 260' of 8-5/8" casing w/250 sacks Pozmix cement; Cement circulated to surface.
 Set 4233' of 5 1/2" casing w/100 sacks common cement.


<u>Formation</u>	<u>Top</u>	<u>Bottom</u>	<u>Formation</u>	<u>Tops and Minus</u>
Sand & Shale	0	260	Anhydrite	795 (+1148)
Shale	260	300	Heebner	3475 (-1532)
Shale & Shells	300	475	Toronto	3499 (-1556)
Sand & Sandy Shale	475	575	Douglas	3519 (-1576)
Shale & Redbed	575	795	Brown Lime	3609 (-1666)
Anhydrite	795	806	Lansing	3634 (-1691)
Shale & Shells	806	1275	Base K.C.	3912 (-1969)
Lime & Shale	1275	1900	Viola	4070 (-2127)
Lime	1900	2225	Simpson	4180 (-2237)
Lime & Shale	2225	3390	Arbuckle	4232 (-2289)
Lime	3390	3520		
Shale	3520	3635		
Lime	3635	3912		
Lime & Shale	3912	4070		
Chert & Cherty Lime	4070	4180		
Shale & Sandy Shale	4180	4232		
Dolomite	4232	4236		
Total Depth		4236'		

STATE OF KANSAS)
)
 COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of Drillers* Log of well drilled in the SW NE SE, Section 32-24-13W, Stafford County, Kansas, to best of my knowledge and belief.

CHIEF DRILLING CO., INC.

 V. Richard Hoover, President

Subscribed to and sworn to before me this 30th day of July, 1958.


 Norris Taylor, Notary Public

My Commission Expires:
 May 19, 1962

PLUGGING
 FILE SEC 32 T 23 R 13W
 BOOK PAGE 130 LINE 26

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 19 1958
 CONSERVATION DIVISION
 Wichita, Kansas