


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County. Sec. 32 Twp. 24s Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines. C S/2 SE SE
Lease Owner Santa-Fe Pipe & Supply, Inc.,
Lease Name Glasscock Well No. B' #2
Office Address Box 562, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed July 28 1961
Application for plugging filed February 9 1967
Application for plugging approved February 10 1967
Plugging commenced March 2 1967
Plugging completed April 25 1967
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4234' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	none
				4-1/2"	4229'	2158.57'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4234' - 4020' - plug
4020' - 3775' - sand
3775' - 3739' - 3 sacks cement
3739' - 225' - pumped 10 sacks gel mud
225' - base - pumped 75 sacks cement

5-29-67

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*

Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of May, 1967

Mary M. Guesnier
Notary Public.

My commission expires July 31, 1970

WELL LOG

15-185-10468-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 32 T.24S R. 13W

FARM GLASSCOCK "B" NO. 2

LOG. S/2, SE,SE


TOTAL DEPTH 4234'

COUNTY STAFFORD CO., KANSAS

COMM. July 17, 1961

COMP. July 28, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 255' w/225 sax.
4 1/2" @ 4229' w/300 sax.

ELEVATION \bar{K} 1941 DF

PRODUCTION Arbuckle

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1967
CONSERVATION DIVISION
Wichita, Kansas

45	Sand
150	Sand & clay
255	Shale & red bed
740	Red bed w/sand streaks
830	Shale
855	Anhydrite
1025	Shale
1745	Shale & shells
1940	Shale & lime
2050	Lime & shale
2090	Lime & sand
2145	Lime
2420	Lime & shale
2420	Lime & shale
2955	Shale
3100	Lime & shale
3400	Shale & lime
3480	XXXXX Lime
3650	Chalky lime & shale
3980	Lime
4082	Lime, chert & shale
4119	Lime & chert
4178	Chert & lime
4220	Simpson sand
4234	Sand & lime
4234	T. D.

State of KANSAS }
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #2 GLASSCOCK "B" well.

Verne A. Morris

Subscribed and sworn to before me this 7th day of August 19 61

My Commission Expires: April 14, 1963

Arthur J. Miles
NOTARY PUBLIC