


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Harvey County. Sec. 36 Twp. 24S Rge. 1 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Cingress Well No. 1
Office Address Liberty Bank Bldg., Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 5, 1959
Application for plugging filed Oct. 5, 1959
Application for plugging approved Oct. 5, 1959
Plugging commenced Oct. 5, 1959
Plugging completed Oct. 5, 1959
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	211'	8-5/8"	211'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3700' to 180' - heavy rotary mud
180' to 134' - plug, 1/4 sk. hulls & 15 sks. cement
134' to 30' - heavy rotary mud
30' to 6' - plug, 1/4 sk. hulls & 10 sks. cement
6' to surface - cellar
rathole - 2 sks. cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.
(Signature) BY: [Signature]
P.O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1959
[Signature]
Notary Public.

My commission expires April 27, 1960

DRILLERS' LOG

Well Owner:	Anderson-Prichard Oil Corporation	SW/4 SW/4 NE/4
Farm Name:	Gingrass Well No. 1	Sec. 36-24S-1W,
Commenced:	9/22/59	Harvey County,
Completed:	10/5/59	Kansas
Total Depth:	3700'	
Casing:	8-5/8" @ 211' cem.	Elevation:
Contractor:	Peel Brothers, Inc.	Production: Dry

Figures below indicate bottoms of formations:

Surface soil and clay	0 -	15
Shale and lime		154
Shale and shells		290
Lime		455
Lime and shale		480
Lime, shale and shells		735
Lime and shale		1265
Lime, shale and shells		1525
Lime and shale		1715
Lime		1850
Lime, shells and shale		2000
Lime and shale		2155
Shale and lime streaks		2300
Lime		2775
Lime and shale		2910
Lime, shale and shells		2990
Lime and shale		3060
Lime, shale and chert		3075
Chert and shale		3111
Chert		3115
Lime		3285
Cherty lime		3323
Lime and chert		3353
Lime		3415
Shale and lime		358 3
Shale, lime and sand		3615
Shale		3640
Sand		3645
Sand and shale		3695
Lime		3700
TD		3700

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1959
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: *Mendell G. Peel*

SUBSCRIBED AND SWORN to before me this 6th day of October, 1959

My commission expires: April 27, 1960

Ruth Brant
Notary Public