



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 29 1962
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. H. J. Plouffe of Olympic Petroleum Co. has this
 date requested permission to plug the following described well:

Mr. J. D. Kimmell guarantees payment of the plugging fee.

Operator's full Name: Olympic Petroleum Company

Complete Address: 204 Columbia Bldg., Tulsa 3, Oklahoma

Lease Name: LaVerne Becker Well No. # 1

Location: SW SE NE Sec. 30 Twp. 15 Rge. 11 (E) (W)

County Russell Total Depth 3378 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. H. J. Plouffe was instructed to plug the well as follows:

8 5/8" 340' Cwc.

Filled hole with heavy mud to 330', set plug with 1/4 sax
hulls, & displaced 25 sax cement thru drill pipe. Mud to
40', 1/2 sax hulls, plug, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
 Conservation Division Agent