

State of Kansas



15-155-20512-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 11, 1978
RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAY 15 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Baker of NCRA has this

date requested permission to plug the following described well:

Mr. Baker guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box 6, Great Bend, Kansas 67530

Lease Name: Barnes Well No. 1

Location: W/2 MW NE Sec. 34 Twp. 24 Rge. 8 (E) (W) X

County: Reno Total Depth 3745' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Baker was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe


at 500'. Pump 25 sacks cement through drill pipe at 200'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole and cement with 2 sacks cement.

8-5/8" surface casing set at 208' w/200 sacks cement.

Very truly yours,


Conservation Division Agent