

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

July 21, 1964

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this  
date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: Linscheid "B" Well No. 1

Location: E/2 NW Sec. 19 Twp. 24 Rge. 7 (E) (W) X

County Reno Total Depth 3514' Oil Well         

Gas Well          Input Well          SWD Well X D & A          Lost Hole         

Mr. Watson was instructed to plug the well as follows:

Fill hole with sand to 3500' and cement with 3 sacks.

Fill hole with mud to 185'. Set rock bridge from 185'

to 175', and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

[Signature]  
Conservation Division Agent