

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 27, 1964

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: Linscheid "A" Well No. 2

Location: W/2 NW Sec. 19 Twp. 24 Rge. 7 (E) (W) X

County Reno Total Depth 3524' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Watson was instructed to plug the well as follows:

Fill hole with sand to 3500' and cement with 5 sacks.

Fill hole with mud to 180'. Set rock bridge from 180'

to 170' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap

hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent