

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 7, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Tomlinson-Kathol Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: Linscheid "A" Well No. 11

Location: W/2 NW $\frac{1}{4}$ Sec. 19 Twp. 24 Rge. 7 (E) (W) X

County Reno Total Depth 3524' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3500' and cement with 4 sacks.

Fill hole with mud to 190'. Set rock bridge from 190'

to 180' and cement hole with 20 sacks. Fill hole with

mud to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,


Conservation Division Agent