



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 5, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Thronton E. Anderson

Complete Address: 300 W. Douglas, Suite 340, Wichita, Kansas 67202

Lease Name: Burling Well No. 1

Location: NW NE NW Sec. 19 Twp. 24 Rge. 7 XX (E) (W) X


County: Renovot Total Depth 3765' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

Fill hole with mud. Push plug to 400' and pump 40 sacks
cement through drill pipe at 40'. Pump 25 sacks cement
through drill pipe at 200'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Bridge rathole and
cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent