

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-28

LOCATION SE. NW. NW

SEC. 21 TWP. 14 RGE. 13-W

Cable Tool

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Sherwood

Operator Mr. Louis M. Mai Address Russell - Kans

Field _____ County Russell

Total Depth 2430 Feet. Plugging Contractor Jayhawk Casing Pulling Co
Russell - Kans.

(Describe briefly the manner in which the well was plugged) Item # 19

No Snaper left in hole - 7' casing set at 2450ft.
75 sacks of cement. Plugged back to 2300ft with sand
& rock. Dumped 5 sacks of cement at 2300ft. shot
off & pulled the 7' casing - mud to 225ft. Set
rock bridge & 30 sacks of cement at 225ft. mud
to 30ft. rock bridge & 15 sacks of cement at
the surface

PLUGGING
FILE SEC 21 T 14 R 13W
BOOK PAGE 134 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1953 11-2-1953
CONSERVATION DIVISION
Wichita, Kansas

C. M. Stouck
District Conservation Agent
Date 10-31-53