

15-015-40246-00 *RP*

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority: Apr. 1/69
Well Plugging Completed: May 12/69

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morris Sitrin Inc.

Complete Address: Box 693 Great Bend, Kans. 67530

Lease Name Bates Well No. 6-A

Location NE SW SW Sec. 10 Twp. 27 Rge. 4E (E) (W)

County Butler Total Depth 2516'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Plg. Co.

Address: Box 405 Chase, Kans. License No. 436

Operation Completed: Hour Day 12 Month May Year 1969

The Above well was plugged as follows:

T.D. - 2516'.

2515' - 4 1/2" cemented - 55 sacks cement.

Perforated - 2505' - 2515'. Bridge plug @ 2502'.

Perforated 2496' - 2481'.

Filled to 2473', 3 sacks cement. 200' - 4 1/2" recovered.

60' - 8 5/8" cemented 60 sacks cement.

Cave at 170' - 4 1/2" yds. Redi-mix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ted. E. Dewey
Well Plugging Supervisor

DATE 5-15-69
INV. NO. 9568-E

BATHS NO. 6A

DRILLED IN: CENTER OF W LINE
OF NE 1/4 OF SW 1/4 OF SW 1/4
SEC. 10-27-4N
BUTLER CO., KANS.

DRILLED BY: H & M DRILLING CO.
WICHITA, KANSAS

DRILLING COMM: NOVEMBER 14, 1958
DRILLING COMP: NOVEMBER 20, 1958

ROTARY

Lime & Shale	43
Lime	60
Lime and Shale	283
Lime Shells	368
Shale and Shells	1260
Lime and Shale	1620
Lime	1843
Lime and Shale	2010
Lime	2190
Lime and Shale	2470
Rotary Total Depth	2516

Run 66' of 8 5/8" surface pipe
cemented with 50 lbs cement

Run 2516' of 4 1/2" casing
cemented with 35 lbs cement

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1959
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
County of Butler)

W. J. Marlean, of lawful age, being duly and
solely sworn on oath says:

I am a resident of Leona, Butler County, Kansas,
and hereby know and on oath state that the above drilling log
covering the Baths No. 6A well located in Sec. 10-27-4N
Butler County, Kansas is true and correct to the best of my
knowledge.

Subscribed and sworn to before
me, a Notary Public, this
1st day of December, 1958

H & M Drilling Company

By _____
Partner

My Commission Expires:
4-24-57

Notary Public