

15-185-10468-0000

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
4-26-67  
STATE CORPORATION COMMISSION  
APR 26 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued February 10, 1967.

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Glasscock "B" Well No. # 2

Location C S/2 SE SE Sec. 32 Twp. 24 Rge. 13 (E) (W) W

County Stafford Total Depth 4234'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 4:00PM Day 25th Month April Year 1967

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 225 sacks. 4229' of 4 1/2" long  
string, cemented with the top of the cement at 3000'. Plug back T.D.  
4020'. Top perforation 3784'. Bottom of the hole was sanded to 3775',  
and cemented with 3 sacks, through the dump bailer. 2200' of 4 1/2" long  
string was recovered from the hole. Hole was squeezed. 10 sacks of Gel-  
Mud and 75 sacks of cement was pumped into the surface pipe, through  
an 8 5/8" swage, to a pressure of 150 lbs, bringing the cement to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Aubie Elving  
Well Plugging Supervisor

DATE 4/26/67

INV. NO. 5118-W