

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02044-00-00  
Spot: W2NWSE Sec/Twnshp/Rge: 16-11S-16W  
1980 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: LUNDY Well #: 1  
County: ELLIS Total Vertical Depth: 3353 feet

Operator License No.: 5252  
Op Name: R. P. NIXON OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3353		410 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2016 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DUANE ATCHERBERG Company: R.P. NIXON OPERATIONS, INC DB Phone: (785) 656-0038

Proposed Plugging Method: Ordered 360 sx 60/40 pozmix 4% gel cement w/500 3 hulls.  
Casing leaks: 2700' - 2720'.  
PBTD-2970'  
5 1/2 casing cemented top to bottom.  
Perforations: 2902' - 2906' and 2947' - 2949'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2016 11:35 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 2852'. Global rigged to tubing, mixed and pumped 150 sx cement w/300 # hulls mixed in. Pulled tubing to 1450'. Rigged to tubing and pumped 150 sx cement w/200 # hulls to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement at 200 psi. Shut in pressure 75 psi. 8 5/8" surface casing full of cement.

Perfs:

Top	Bot	Thru	Comments
2947	2949		
2902	2906		

Remarks: GLOBAL CEMENTING CO - NO TICKET #

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

OCT 04 2016

CM

AUG 16 2016

SEP 06 2016

CONSERVATION DIVISION  
WICHITA, KS

Form P-2/3  
*Nedra Dennis*