

TO:

API Well Number: 15-073-24034-00-00

Spot: N2S2SW

Sec/Twnshp/Rge: 20-22S-10E

990 feet from S Section Line, 1320 feet from W Section Line

Lease Name: BROWNING

Well #: 26

County: GREENWOOD

Total Vertical Depth: 2384 feet

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2384		150 SX
SURF	8.625	202		100 SX

Operator License No.: 34479

Op Name: PATTERSON OPERATIONS LLC

Address: 618 N. WESTCHESTER DR.  
ANDOVER, KS 67002

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2016 1:00 PM

Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC

Proposal Rcvd. from: HARRY PATTERSON Company: \_\_\_\_\_ Phone: (316) 259-9166

Proposed Plugging Method: According to Kansas Corporation requirements.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2016 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2225', pumped 25 sxs cement, pulled tubing to 890' pumped 15 sxs cement, pulled tubing to 258' pumped 80 sxs cement to surfaced, perfed well @ 890' & 250', gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2328	2334		
2308	2318		
2296	2300		

RECEIVED  
KCC DIST # 3  
SEP 12 2016  
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Duff  
KANSAS CORPORATION COMMISSION (TECHNICIAN)  
Received SEP 16 2016  
CONSERVATION DIVISION WICHITA, KS  
OCT 04 2016  
Nedra Olewicki  
Form CP-2/3

810 E 7TH  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. **2862**  
 Foreman Rick Ledford  
 Camp Eureka Ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
9-16-16	1044	Browning # 26	20	22S	10E	GW	Ks	
Customer <u>Patterson Operations</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>1018 Westchester Dr.</u>			105		<u>Dave G.</u>			
City <u>Andover</u>			110		<u>Zach A.</u>			
State <u>Ks</u>			114		<u>Wick L.</u>			
Zip Code <u>67002</u>			121		<u>Gary M.</u>			

Job Type P.T.A. Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/4"  
 Casing Depth 2384' Hole Size \_\_\_\_\_ Slurry Wt. 14# Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2" Cement Left in Casing \_\_\_\_\_ Water Gal/SK 7.0 Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting - Plugging orders as follows:  
25 sks @ 2225' (w/hulls + 2% caliz water)  
15 sks @ 870'  
80 sks @ 258' to surface  
120 sks Total

API # 15-073-24034

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	25	Mileage 1st well of 2	3.95	98.75
C203	120 sks	60/40 Permox cement	12.75	1530.00
C206	410 #	470 gel	.20	82.00
C205	58 #	2% caliz. -> bottom plug	1.02	30.00
C214	20 #	hulls	.45	9.00
C103A	5.16	ten mile log haul tol	m/c	345.00
C113	3 hrs	80. Bbl WAC. 72K	85.00	255.00
C206	200 #	gel spacers between plugs	.20	40.00
Received KANSAS CORPORATION COMMISSION SEP-16-2016 CONSERVATION DIVISION WICHITA, KS			Subtotal	3139.75
			Sales Tax	235.48
Authorization _____ Title _____			Total	3375.23

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.