

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21587-00-00
Spot: SWSESW Sec/Twnshp/Rge: 14-33S-6W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: FLINN Well #: 2
County: HARPER Total Vertical Depth: 4530 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4526		160 SX
SURF	8.625	314		225 SX
T1	2.375	4487		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/13/2016 12:00 AM
Plug Co. License No.: 34141 Plug Co. Name: MOHEGAN WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN DISKIN Company: MOHEGAN WELL SERVICE, LLC Phone: (316) 303-4691

Proposed Plugging Method: Per KCC requirements.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2016 4:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Set CIBP @ 4350' -2 sxs cement. Perforated casing at 1100', spotted 35 sxs cement, thru tubing. Tagged TOC@980'. Pulled tubing to 700', spotted 35 sxs cement. Tagged cement at 560'. Pulled tubing to 360' and circulated cement up backside and filled inside of casing to 0'.

Perfs:

Top	Bot	Thru	Comments
4396	4464		

Remarks: BASIC ENERGY SERVICES, COMMON 3% CEMENT, DENIED TA.

Plugged through: TBG

District: 02

Signed

[Signature]
(TECHNICIAN)

OCT 04 2016

Form CP-2/3

[Signature]